

Stockton Street Enhancement Project

Prepared for:
Chinatown Community Development Center
and
The City and County of San Francisco
Department of Parking and Traffic

Prepared by:

*CHS Consulting
Group*



500 Sutter Street, Suite 216
San Francisco, CA 94102
(415) 392-9688

June 30, 2003

TABLE OF CONTENTS

Executive Summary	5
1.0 Introduction	7
2.0 Community and Stakeholder Meetings	10
2.1 Community Outreach	10
2.2 Stakeholder Meetings	10
3.0 Existing Conditions	11
3.1 Data Collection	11
3.2 Data Analysis	11
3.2.1 On-street Parking and Loading Conditions	11
3.2.2 Double Parking Conditions	13
3.2.3 Pedestrian Conditions	14
3.2.4 Accident Data	15
3.2.5 MUNI Operations	16
3.3 Additional Community Concerns	18
4.0 Goals and Objectives	19
5.0 Project Alternatives and Evaluation	20
5.1 Process	20
5.2 Evaluation Criteria	20
5.3 Evaluation	20
5.4 Alternatives	22
5.4.1 Management Improvements	22
5.4.2 Operational Improvements	26
5.4.3 Physical Improvements	30
6.0 Preferred Alternatives	50
6.1 Phase One Improvements	50
6.2 MUNI Improvements	53
6.3 Major Physical Improvements	55
6.4 Cost Estimates and Implementation	55



LIST OF TABLES

Table 1. Data Collection Periods by Mode	11
Table 2. On-Street Parking Supply and Occupancy and Average Duration	12
Table 3. Existing MUNI Service on Stockton Street	16
Table 4. Existing Weekday Midday MUNI Operations on Stockton Street	17
Table 5. Summary of Benefits and Impacts for Each Alternative	21
Table 6. Comparison of Weekday and Sunday Parking Duration	25
Table 7. Order of Magnitude Costs	56



LIST OF FIGURES

Figure 1. Study Area	7
Figure 2. Stockton Street Corridor	8
Figure 3. Presentation at a Community Workshop	10
Figure 4. Boxes Stored on Stockton Street	12
Figure 5. Congested Corner on Stockton Street	14
Figure 6. Crowded Mid-Block Conditions	14
Figure 7. Bunched Buses on Stockton Street	17
Figure 8. All-Door Boarding on Stockton Street	26
Figure 9. MUNI Pre-Paid Fast Pass	27
Figure 10. Sample Stockton Street Shuttle Route	29
Figure 11. Passengers Boarding Low Floor Bus	29
Figure 12. Example of a Delineated Pedestrian Walkway	30
Figure 13. Locations of Proposed Corner Bulb-Outs	32
Figure 14. Travel Time Changes with Corner Bulb-Outs	33
Figure 15. MUTCD Standard Striping for Scramble Intersections	34
Figure 16. Existing Bi-Lingual Pedestrian Crossing Sign	34
Figure 17. Ped-Mount Newstrack in San Francisco	36
Figure 18. Example of Tread Tape on Sub-Sidewalk Elevator Doors	37
Figure 19. Example of a Modified Bus Shelter	37
Figure 20. Option 1: Southbound Bus Queue Jumps	40
Figure 21. Travel Time Changes with Option 1: Southbound Bus Queue Jumps	39
Figure 22. Option 2: Southbound Bus-Only Lane	42
Figure 23. Travel Time Changes with Option 2: Southbound Bus-Only Lane	41
Figure 24. Option 3: Northbound Bus- and Truck-Only Lane	44
Figure 25. Travel Time Changes with Option 3: Northbound Bus- and Truck-Only Lane	45
Figure 26. Option 4: Widened Sidewalks	46
Figure 27. Travel Time Changes with Option 4A: Widened Sidewalks	47
Figure 28. Travel Time Changes with Option 4B: Widened Sidewalks with Traffic Diversion	48
Figure 29. Example of a Corner Bulb-Out	51
Figure 30. Existing Bi-Lingual Scramble Intersection Sign	51
Figure 31. Pedestrian Scramble Signal at a Stockton Street Intersection	52
Figure 32. MUNI Proof-of-Payment Logo	53



LIST OF APPENDICES

- Appendix A. Public Workshop Meeting Summaries
- Appendix B. Existing Enforcement Jurisdictions and Fines
- Appendix C. Results of CORSIM Modeling of Major Physical Improvements
- Appendix D. Cost Estimates for Major Physical Improvements



